



TRIDENT CONSULTANCY SERVICES

PLOT NO. 45, FIRST FLOOR, GIRIRAJ COMPLEX ZONE-2,
M.P. NAGAR, BHOPAL – 462011, India

Email id: tsctrident1126@gmail.com Mob: 9244971257

BOQ FIRE HYDRANT SYSTEM

To,
Mr. Kashif
Bhopal

Date – 20/05/2026

Dear Sir,

We thank you for the keen interest shown by you in our fire fighting equipment and value-added services. As desired, we take pleasure in quoting you our best rates and look forward to your valued order.

S.NO.	DESCRIPTION		QTY	RATE	AMOUNT
01.	Providing/Fixing of M.S. “B” class pipe IS: 1239 including cutting, threading, welding etc. with bend, tee and flange complete with nuts and bolts, elbows, joints, reducers rubber insertion including fixing the pipe with suitable flat iron strip clamp/bracket including painting with one coat of primer and approved make and shade including all steel work complete as required. (MAKE: JINDAL/APOLLO) 100 MM 80 MM 65MM 32MM 25MM		30 Mtr 20 Mtr 20 Mtr 12 Mtr 80 Mtr	1450/- 1100/- 830/- 590/- 510/-	43,500/- 22,000/- 16,600/- 7,080/- 40,800/-
02	Providing/Fixing of Monoblock Fire Fighting pump set suitable for automatic operation consisting of the following as per the specification. a) Horizontally mounted. Centrifugal type single/multi stage fire pump having cast iron body. Bronze impeller, stainless steel shaft. including bypass arrangement. (MAKE: LUBI) 20 HP 5 HP		01 Set 01 Set	95,000/- 40,000/-	95,000/- 40,000/-
03.	Pump Control Panel with all necessary wiring work including control and instrumentation, etc complete. With required cable.		1Set	35,000/-	35,000/-
04.	Providing/Fixing of First- Aid Hose Reel wall mounting swinging complete with drum. Breket, 20 mm dia X 30 mtr. Long high pressure Hose Reel with Dunlop hose 1/4” dia with ABS nozzle complete with valve/tubing etc. Make : ARMOR/ULTRAFIRE/NEWAGE		05Nos	5,200/-	26,000/-

05.	Providing/Fixing of 2 way fire brigade inlet connection (suction collecting head) consisting of 63 mm dia instantaneous type male/female coupling with built-in check valve and 150 mm dia flanged complete with bolts. Nuts and rubber insert insertions as required.		01 No	6,500/-	6,500/-
06.	Providing/Fixing butterfly valve IS: 13095. PN 1.0. ISI mark complete with 3 Nos. matching flanges. Rubber insertion, nuts, bolts and washer etc. a)100mm dia Make : ARMOR /Kartar/Kranti		03 Nos	4,500/-	13,500/-
07.	Providing/Fixing of Non return valve as per IS: 5312 or its latest version, brass hing pin, nuts and bolts, welding, washers, rubber gasket, insertion etc. complete. a) 100 mmdia Make : Kartar/Kranti		01 Nos	5,500/-	5,500/-
08.	Providing/Fixing of pressure gauge dial size 100 mm range 0-10 Kg/cm sq. complete with isolation valve & siphon. Make : HGuru		1 No	1,400/-	1,400/-
09.	Providing/Fixing pressure switch complete with isolation with all accessories.		01 No	3,000/-	3,000/-
10.	Supplying , installing, testing and commissioning of Bronze Ball valve with (suitable for test pressure of not less than 15 Kg/sqm of the following size including providing necessary union/flange.		06 No.	1,500/-	9,000/-
11	Providing & Fixing of spring-loaded Air Release Valve suitable for the pressure of 15 Kg / sq.cm including flanges, nuts, bolts, washers etc. complete as required.		01 No.	5,000/-	5,000/-
12.	Providing/Fixing of First- Aid Hose Reel wall mounting swinging complete with drum. Breket, 20 mm dia X 30 mtr. Long high pressure Hose Reel with Dunlop hose 1/4" dia with ABS nozzle complete with valve/tubing etc. Make : NEWAGE/ARMOUR		06 No.	5,500/-	33,000/-
13	Single Door Fire Hose Box suitable for storing 1 nos 15 mtr hose and one nozzle. Light weight & wall mounted/self standing finished with post office red colour.		05 No.	4,000/-	20,000/-
14	15 mtr length Rubber inner lining with suitable rubber compound which gives flexibility, durability & Better resistance. 63 mm		05 No.	5,300/-	26,500/-
15	S.S Branch pipe & Nozzle 63mm		05 No.	2,100/-	10,500/-

16	Forged Brass Sprinkler		38 No.	510/-	19,380/-
18	Advanced Microcontroller based Fire Alarm Panel 4 Zones, 16*2 character LCD Display, Mains, A.C. Fail, fuse, Charging, Rev. Batt. Indication, Zone wise fire, open, short LED indications, Zone healthy indications, Zone isolations facility through the switch, Extra potential free contact for fire & fault, Trickle & Fast Charging facility, Reset, alarm cancel, lamp test, controls etc. Make : Ravel/Agni		01 No.	12,500/-	12,500/-
19	The re-settable operation, Compatiability with any conventional fire alarm system, wall mount facility, normal Green-LED blinking 14 sec, steady glow of Red LED indicates the alarm condition, suitable for malls, restaurants etc, wheeling tones available Make – Ravel/Agni		05 No.	1100/-	5,500/-
20	24 DC Operation, Compatibility with any conventional fire alarm system, wall mounted facility connector is plug-in-type suitable for malls, restaurants, residential etc. Make – Ravel/Agni		05 No.	1250/-	6,250/-
21	Laying of 1.5mm*2 core copper cable for connection of manual call point, Hooter, and control panel. 4mm*3 core		350 Mtr	105/-	36,750/-
22	Smoke Detectors Make – Ravel/Agni		85 No.	1250/-	1,06,250/-
23	ABC Powder Based Portable Fire Extinguishers 6 KG Warranty- 1 year		05 No.	1800/-	9,000/-
24	CO2 Type Fire Extinguishers 4.5 KG Warranty-1 Year		1 No.	5,000/-	5,000/-
25	Supplying, fabricating, and STRUCTURAL STEEL SUPPORTS such as MS channels, angles, flats, rods as required at site with anchor fasteners, clamps, threaded rods, nuts, bolts, washers etc. complete with painting.		150kg	110/-	16,500/-
26	Transportation and Installation for whole project.		1 Job	1,50,000/-	1,50,000/-
27	Fire NOC Consultation Fee with Fire Plan (Provisional NOC/Fire Approval Plan)		1 Job	60,000/-	60,000/-
	TOTAL				887,010/-

	GST @ 18%				159,661/-
	GRAND TOTAL				1,046,671/-

Terms and Conditions: -

1. Quotation is valid for 10 days from the date of issue.
2. The material delivery can start within 07-10 days of the advance payment and confirm the Work order and depending on the client's requirement or will.
3. Work will be completed within 30 days from the date of receiving the P.O, However if the completion of the work is delayed beyond the agreed contractual date for reasons under clients control as listed out here under but not limited to them ,we shall be entitled to suitable re adjustments in the period of completion by mutual consent and the contract will stand amended to that extent. Delay in release of advance or progress payments due to us beyond 10 days from the bill date.
4. Length of pipe, Electrical Wire, Smoke Detectors, Hooter, sprinklers and Ball Valve can be change at the time of final installation.
5. All waterproofing of pump house/ tanks, water inlet pipe to pump house, Cable, Wire, electrical incoming supply to pump house for pump room will be provided by Client.
6. The client must provide all necessary documents, Building permission, Approved Building Layout Plan, Ownership document, Property Tax Id.
7. . Payment 70% Advance with P.O, and 20% after material dump and 10% after completion of installation just after SITC and demonstration
8. Payment will be done in any mode; cheque/ D.D./NEFT/RTGS.